

Beneficiar: UAT PRUNISOR  
 Executant:  
 Proiectant: Urban Planning Architecture  
 Obiectivul: Demolare cladire existenta C1 si construire gradinita cu doua grupe  
 Obiectul: 2 Montaj utilaje tehnologice  
 Stadiul fizic: 1 Montaj echipamente



## Anexa explicitare norme

Nr.	Simbol	Denumirea resursei	Tip	U.M.	Cantitate	Pretul unitar (fara TVA) - Lei -	Valoarea (fara TVA) - Lei -
0	1	2	3	4	5	6	7 = 5 X 6

### EF03A1[1]

Panou fotovoltaic 500 W policristalin

1	12061	Tablou de distributie electria	Lista	buc	1.000		
1.1	5500598	Cutie cu contactor 16a 380 V ex nid 2938/1971 simb.7045	Mat	buc	1.000		
2	2100402	Ciment II B 32,5 (M 30) saci	Mat	kg	2.410		
3	2200525	Nisip de rau si lacuri sortat si nespalat, 0.0- 7.00 mm	Mat	mc	2.410		
4	5827702	Surub pt.fundatii grosolan a m 16X 200 GR. 4.8 S 2350	Mat	buc	9.642		
5	5840558	Piulita hexagonala grosolana a m 16 GR. 5, S 922	Mat	buc	9.642		
6	5882257	Saiba prec.plata pt.met a m 18 OL34 S 5200	Mat	kg	2.410		
7	6202806	Apa industriala in cisterne pentru lucrari de drumuri si terasamente	Mat	mc	2.410		
8	7309326	Carpe de sters, din bumbac de orice culoare	Mat	kg	2.410		
9	17130	Instalator electrician	Man	ora	24.104		
<b>TOTAL EF03A1[1]</b>						buc	

### RPIA51A1-1

Montare vas de expansiune de 80 L

1	13801	Racord olandez L2 negre-zincate	Lista	buc	8.928		
1.1	4121682	Racord olandez et plana U1 S482 DN 15 1/2 zn	Mat	buc	8.928		
2	4114811	Teu fonta mal B1 S479 32X 15X32 11/4X 1/2X11/4 F1	Mat	buc	2.410		
3	6103294	Vopsea minium de plumb V 351-3 ntr 90-80	Mat	kg	2.410		
4	7322940	Fuior cinepa	Mat	kg	2.410		
5	17150	Instalator incalzire + gaze	Man	ora	24.152		
<b>TOTAL RPIA51A1-1</b>						buc	

### RPIA57C#

Montarea pompelor-P. de circulatie

1	IL06D	Pompe de circulatie a apei calde	Lista	buc	1.000		
1.1	5786019	Pompa de alimentare cu apa tip duplex,D= 3",motor0.75KW	Mat	buc	1.000		
2	20010013	Material marunt	Mat %	%	1.500		
3	17150	Instalator incalzire + gaze	Man	ora	6.000		
4	7602	Aparat de tractiune (tirfor) pentru 1,5 tone forta	Utj	ora	0.200		

Nr.	Simbol	Denumirea resursei	Tip	U.M.	Cantitate	Pretul unitar (fara TVA) - Lei -	Valoarea (fara TVA) - Lei -
0	1	2	3	4	5	6	7 = 5 X 6
5	3008	Aparat de sudura in mediu de argon tip tv-350 27kva	Utj	ora	0.250		
TOTAL RPIA57C#					BUCATA		

IA01C02>1 Montaj pompă de căldură							
1	6103294	Vopsea minium de plumb V 351-3 ntr 90-80	Mat	kg	0.241		
2	7322940	Fuior cinepa	Mat	kg	0.121		
3	7345564	Snur din azbest 22 MM	Mat	kg	1.205		
4	17150	Instalator incalzire + gaze	Man	ora	57.850		
TOTAL IA01C02>1					buc		

Director	Sef proiect	Ofertant
----------	-------------	----------