



Elementul		Marca	Ø	Lungime	Nr. Buc.		Lungimi pe Ø		
Denumire	Nr. elem.				Intr-un elem.	In toate elem.	BST 500S		
							8	14	16
G1	2	1	16	5.20	3	6			31.20
		2	16	3.10	5	10			31.00
		3	8	1.05	24	48	50.40		
G2	1	4	14	3.10	5	5		15.50	
		5	8	1.15	17	17	19.55		
G3	1	6	16	5.25	4	4			21.00
		7	16	3.10	4	4			12.40
		8	8	1.35	29	29	39.15		
Lungimi/Ø (m)							109.10	15.50	95.60
Greutate/m (kg)							0.395	1.210	1.580
Greutate/Ø (kg)							43	19	151
TOTAL (kg)							213		

Otel: BST 500S (S500C)
Beton: C20/25 -XC2- Cl 0,20 - 0.... 16- A/C 0.60 - S2 - CEM II A-S 32.5
Strat de acoperire cu beton: 25mm

				PROIECTANT GENERAL S.C. MOUA INDUSTRIAL SRL CUI 46338868		Clasa de importanta: III Categoria de importanta: C	
LACHELI CONSULT SERV s.r.l. CLUJ-NAPOCA, str. Fantanetele nr. 63-65, ap. 254 J12/5686/2022; CUI 46811019				Beneficiar: COMUNA TAGA		Faza P.T.+D.E.	
Sef proiect: Arh. Mihai Pascalau Proiectat: Ing. Aurelian Achim Desenat: Ing. Aurelian Achim				DEMOLARE CONSTRUCTIE EXISTENTA, CONSTRUIRE CAPELA MORTUARA, AMENAJARI EXTERIOARE, IMPREJMUIRE TEREN, RACORDURI SI BRANSAMENTE LA UTILITATI loc. Taga, str. Principala, nr. 7, jud. Cluj		Proiect nr. 09/2025	
Data: 09.2025 Scara: 1:50(1:20)				Plan cofraj si detalii armare G1, G2 si G3 la parter		Plansa nr. R07	