

③ Ø8/20 BST 500S L=0.95m

Marica	Denumire cmc	Lungime (m)	Vol./buc. (mc)	Buc.	Volume (mc)
1	Osonoroaba	15 x 15	4.00	0.090	10
2	Arbaletrier	20 x 20	4.60	0.184	2
3	Coarda	15 x 20	6.00	0.180	2
4	Agatator	20 x 20	3.10	0.124	1
5	Contrafrise	20 x 15	2.20	0.066	2
6	Pana	20 x 25	3.80	0.190	1
7	Pana	20 x 25	4.90	0.245	3
8	Pana	20 x 25	5.20	0.260	3
9	Pana	20 x 25	4.50	0.225	3
10	Orest	5 x 20	1.45	0.015	46
11	Capriori	15 x 20	6.60	0.198	10
12	Capriori (mc)	10 x 20	4.20	0.084	64
Total/unitate (mc)					12.29

emn de brad clasa C24 de calitate, uscat si ignifugat.

Otel: BST 500S (S500C)

Beton: C20/25 - XC2 - Cl 0.20 - 0..... 16- A/C 0.60 - S2 - CEM II A-S 32.5

Strat de acoperire cu beton: 25mm






**PROIECTANT GENERAL**  
**S.C. MOUA INDUSTRIAL SRL**  
**011 46338868**

**LACHELI CONSULT SERV s.r.l.**  
LUJ-NAPOCA, str. Fontanelele nr. 63-65, ap. 254  
J12/5686/2022; CUI 46811019

Beneficiario: COMINA TAGA

DEMOLARE CONSTRUCTIE EXISTENTA, CONSTRUIRE  
CAPELA MORTUARA, AMENAJARI EXTERIOARE,

	Numele	Semnatura	Data
Sef proiect	Arh. Mihai Pascolau		09.2025
Proiectat	Ing. Aurelian Achim		Scara
Desenat	Ing. Aurelian Achim		1:50

str. Principala, nr. 7, jud. Cluj

Plansa nr.